Sl No	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
5	KSRB 4-1.6 ; Providing and laying in position **plain cement concrete of mix 1:2:4** with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation, plinth and cills**, ncluding cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. **Page No.13, Item No. 4.6 PWD SR 2018-19**	Cum							
	Coping Concrete		4	350.00	0.20	0.10	28.00		
	Vent Concrete		2	150.00	0.45	0.10	13.50		
	Basic Rate	5422.00					**41.50**	5747.32	**238514.00**
	Area Weightage @ 6%	325.32							
	Total	**5747.32**							
	Providing **precast slab of 100 mm thick** including cost of all materials, labour, curing, transportation, loading unloading, etc., complete as per the direction of engineer in charge- Data rate	Sqm							
	RCC Drain Slab		2	137.00	0.90		246.60		
							246.60	2337.00	**576304.00**
	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with op and bottom width 114 and 165 mm espectively, 400mm high and 450mm in length inished with CM 1:3 plastering and finishing utting including formwork, curing, including cost f materials, labour charges of machinery, loading nd unloading, lead and lift, transportation e.,complete **Page No. 27 / Item No. 5.30 PWD R 2018-19**	No							
	erb Stone		2	350.00			1556		
				0.45					
	Basic Rate	408.00					**1556**	432.48	**672747.00**
	Area Weightage @ 6%	24.48							
	Total	**432.48**							
	RB 15-19.1 : Providing and applying ready mix ning coat **over concrete** / masonry / asbestos ent sheet / plastered surfaces including aring the surface after thoroughly cleaning of grease, dirt and other foreign matter, and sand ering including cost of materials, labour, plete as per specifications. **Page No. 124 / No. Item No. 15.80, PWD SR 2018-19**	Sqm							
	Stone Painting		2	350.00		0.35	245.00		
	Basic Rate	37.00					**245.00**	39.22	**9609.00**
	Area Weightage @ 6%	2.22							
	Total	**39.22**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
9	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.**Page No. 124 / Item No. Item No. 15.81, PWD SR 2018-19**	Sqm							
			Qty Vide Item No. 8				245.00		
	Basic Rate	85.00					**245.00**	90.10	**22075.00**
	Area Weightage @ 6%	5.10							
	Total	**90.10**							2231525.00
	Sub Total								**2211894.00**
	GST @ 12%						267783.00		**265427.00**
	Third Party Inspection Charges @ 1%						642.00		**22119.00**
	Add for unforseen and rounding off	L/S							~~560.00~~
								Total	**2500000.00**
	Rupees Twenty Five Lakh(s) Only								

Certificate:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per P.W.D S.R of 2018-19.
3 This work included under 2017-18 POW Grant.
4 The provisions were made in this estimate are necessary and adequate.
5 This works come under B.B.M.P. limits.

Assistant Engineer
Ward No. 09

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Vidyaranyapura Sub Division

7/01

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

7/01

Technical Sanction
Accorded For ...25.00 Lakh
Head of A/C.....P.1771
CER NO :....201 Dt: 08-01-2019

TA CE (YNK)

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of work: Estimate for Improvements to Drains at Ganesh Temple Road in 4th Block BEL layout in Ward No. 09 (Vidyaranyapura) Vidyaranyapura Sub Division.

Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
						Est Cost Rs.		2500000.00
KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 **Page No. 143 / Item No. 19.1, PWD SR 2018-19**	Cum							
Desilting of Drains 4th block BEL LO Ganesh Temple Road		2	350.00	0.45	0.45	141.75		
Basic Rate	130.00					**141.75**	250.24	**35472.00**
Add loading and unloading Charges **It No 17.1 KSRRB M 100-1**	68.00							
Average weight of earth 1.28 tonne / kg for 11.90 Km = 1.28 T X 11.90Km X 2.5 / km= 38.08	38.08							
	236.08							
Area Weightage @6%	14.16							
Total	**250.24**							
Removing and refixing stone slabs of drains and pointing in CM (1:3) **Page No. 27 / Item No. 5.33 PWD SR 2018-19**	Sqm							
Consider 25%		2	350.00		1.35	945.00		
						283.50		
Basic Rate	105.00					**661.50**	111.30	**73625.00**
Area Weightage @ 6%	6.30							
Total	**111.30**							
Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete **Page No. 27 / Item No. 5.31.1 PWD SR 2018-19**	Sqm							
Consider 25% Damaged Slabs		Vide Item No. 2				73.71		
Basic Rate	700.00					**73.71**	742.00	**54693.00**
Area Weightage @ 6%	42.00							
Total	**742.00**							
SRB 5-14 : Providing and constructing load earing wall with solid concrete blocks of size **00x150x200 mm** having block density not ssthan 1800 kg/m3 and having a minimum erage compressive strength 4.00 N/mm2 nfirming to IS 2185 (Part) : 2005 and nstructed with CM 1:4 , as per IS 2572:2005 luding cost of all materials, labour charegs, affolding, curing complete as per specifications S No.5.4 **Page No. 27 / Item No. 5.26.2, PWD 2018-19**	Sqm							
		4	350.00		0.40	560.00		
Basic Rate	924.00					**560.00**	979.44	**548486.00**
Area Weightage @ 6%	55.44							
Total	**979.44**							